INFORMATION Sheet



September 5, 2019 4090-FLOJV-HEAPS-490-ZR-CM-100002

HEATHWALL PUMPING STATION CHANGE OF WORKING HOURS

Works at our Heathwall Pumping Station site are progressing well, and we are now moving to the next phase of excavation on both of our on-site shafts.

Within our cofferdam we are excavating a shaft to intercept overflows from the Pumping Station. We have now dug down to 14m, lining the structure with pre-cast concrete segments. We will now change technique and construct the remaining 12m by excavating down and using sprayed concrete to line the shaft.

Our in-land combined sewage overflow (CSO) shaft has been excavated to 30m below ground and we will continue constructing this using an underpinning method, installing pre-cast segment rings to line the shaft below the existing rings that are grouted in place. Once we have excavated 2m further, we will move to sprayed concrete technique for the remainder of the CSO shaft, down to 54m.

To facilitate this new phase of works, our working hours are changing to 24hrs from Monday to Friday beginning Monday 9 September until February 2020.

In order to carry out this work, we will require the use of excavators on the surface to manage spoil from the tunnel as well as within the shaft to carry out the work, spraying equipment within the shafts, as well as a silo and pumping equipment on the surface. We will also have a crane on site. As the works are taking place 24hrs the site will require lighting during the evenings/nights.

If you have any queries during this period, please feel free to contact the Tideway 24hr Helpdesk on 08000 30 80 80 or email <u>helpdesk@tideway.london</u>

If you are interested in being be kept up to date with our works then please contact <u>communityrelations@tideway-central.london</u>

KEY INFO

Key information here

Working hours:

- 24hrs Monday to Friday
- 08:00 13:00 Saturday

What to expect:

- Site Lighting 24hrs
- Deliveries to site

24 HOUR HELPDESK 08000 30 80 80

helpdesk@tideway.london | Freepost TIDEWAY www.tideway.london

- Sprayed Concrete Lining within shafts
- Some surface works

What we will do:

 Keep you informed of upcoming works

